

	A	B	C	D	E	F	G	H
1	Attachment A - Original Bid Schedule of Materials & Services							
2					Date:		Preparer:	
3	Project Name: BOS Medial Wall Implementation				Contractor:			
4	TESMA No. : TA568				Contractor Order No.:			
5	Lease:				Other Contractor ID:			
6	BOS- 500 WEST TEMPLE, LOS ANGELES				Materials Cost (Taxable Items)		Labor/Service Cost	
7	Mfr	Description	Part/Reference No.	Qty	Unit	Extended	Unit	Extended
8	Station Cabling			Per 6.2.1				
9	General Cable	GenSPEED 6000 CMP blue - for HDBase-T and Control (1000 FT)	7131900	1	0.00	0.00	0.00	0.00
10	Panduit	Corrugated Loom Tubing (1 lot)	CLT150F-X20	1	0.00	0.00	0.00	0.00
11	Terminating Blocks/Patch Panels			Per 6.2.2 & 6.2.5				
12	Panduit	48 Port Patch Panel - Modular	CP48BL	1	0.00	0.00	0.00	0.00
13	Panduit	RJ45 Category 6 Mini-Com Jack - Blue	CJ688TGBU	100	0.00	0.00	0.00	0.00
14	Panduit	Vertical Cable Manager - 6"	PRV6	3	0.00	0.00	0.00	0.00
15	Panduit	Door for 8" Vertical Cable Manager - 6"	PRD6	3	0.00	0.00	0.00	0.00
16	Panduit	Horizontal Cable Manager - 2RU	WMPH2E	2	0.00	0.00	0.00	0.00
17	Panduit	Rack Filler Panel - 1RU	DPFP1	0	0.00	0.00	0.00	0.00
18	Panduit	24 Port Patch Panel - Modular	CP24BL	0	0.00	0.00	0.00	0.00
19	Panduit	48 Port Category 5e Punchdown Patch Panel	DP48SE88TGY	0	0.00	0.00	0.00	0.00
20	Panduit	Wall Mount Bracket for 48 Port Patch Panel (in MPOE)	WBH2	0	0.00	0.00	0.00	0.00
21	Patch (CAT 6) Cords			Per 6.2.3				
22	Panduit	5 foot - Blue	UTPSP5BU	10	0.00	0.00	0.00	0.00
23	Panduit	7 foot - Blue	UTPSP7BU	20	0.00	0.00	0.00	0.00
24	Panduit	10 foot - Blue	UTPSP10BU	20	0.00	0.00	0.00	0.00
25	Panduit	10 foot - Off White	UTPSP10Y	0	0.00	0.00	0.00	0.00
26	Equipment Racks			Per 6.2.5				
27	Hoffman	19" wide 4 Post Rack, 45 RU Round Hole (Black)	E4DR19FM45U	2	0.00	0.00	0.00	0.00
28	Startech	25U 4 Post Server Open Frame Rack	4POSTRACK25	0	0.00	0.00	0.00	0.00
29	Startech	25U 4 Post Server Open Frame Rack Nuts	CABCAGENUTS	0	0.00	0.00	0.00	0.00
30	Startech	25U 4 Post Server Open Frame Rack Screws	CABSCREWS	0	0.00	0.00	0.00	0.00
31	Cooper B-Line	3" spacer	STD108DET4	4	0.00	0.00	0.00	0.00
32	Cooper B-Line	Cable Tray (feet)	SB-17-12-Y2N	50	0.00	0.00	0.00	0.00
33	UPS							
34	APC	APC Smart-UPS 5000VA 208V Rackmount/Tower	SURTD5000RMLP3U	2	0.00	0.00	0.00	0.00
35	APC	APC Smart-UPS 5000 Battery Back-up	SURT192RMLBP3U	2	0.00	0.00	0.00	0.00
36	APC	APC Basic Rack-Mount PDU - Power Distribution Strip - AC 208V - 30 AMP	AP7584	2	0.00	0.00	0.00	0.00
37	SWITCHING							
38	Cisco	Catalyst 3850 48 Port UPOE IP Base	WS-C3850-48U-S	2	0.00	0.00	0.00	0.00
39	Cisco	SMARTNET 8X5XNBD Cisco Catalyst 3850	CON-SNT-WS3548US	2	0.00	0.00	0.00	0.00
40	Cisco	North America AC Type A Power Cable	CAB-TA-NA	2	0.00	0.00	0.00	0.00
41	Cisco	1100W AC Config 1 Secondary Power Supply	PWR-C1-1100WAC/2	2	0.00	0.00	0.00	0.00
42	Cisco	Catalyst 3850 2x10GE Network Module	C3850-NM-2-10G	1	0.00	0.00	0.00	0.00
43	Cisco	CAT3850 Universal K9 Image	S3850UK9-33SE	2	0.00	0.00	0.00	0.00
44	AV Equipment List							
45	Planar	Direct light DLX-1.8 1.8MM LED Videowall System (12W X 12H) Easy Align Mounting, Direct light control software, Video and power interconnect cables Native UHD 4K 3840 X 2160 Pixel Resolution for full 12X12 Wall	998-0702	144	0.00	0.00	0.00	0.00
46	Planar	Cable Assy, PWR, DC, 48V (200FT)	175-1124	28	0.00	0.00	0.00	0.00
47	Planar	Cable cntrl Interconnect RJ25 1.2M	903-1494	144	0.00	0.00	0.00	0.00
48	Planar	Visual Control Station VCS 12X12	998-0381	1	0.00	0.00	0.00	0.00
49	Planar	Cable PWR C19 US 15FT ps module	903-0639	15	0.00	0.00	0.00	0.00
50	Planar	Assy MFG DLI Box HD Base T	750-2238	4	0.00	0.00	0.00	0.00
51	Planar	Assy MFG RPS (remote pwr supply) Triple 110/220V	750-2190	7	0.00	0.00	0.00	0.00
52	Planar	VC 4HDMI DP loop	750-2172	1	0.00	0.00	0.00	0.00
53	Planar	Sheet Metal Mount link Bracket	572-4431	120	0.00	0.00	0.00	0.00
54	Planar	Sheet Metal Mount link Bracket	572-4722	120	0.00	0.00	0.00	0.00
55	Planar	Easy Align Mount Assembly 2X2 2wide by 2 tall includes power distribution	998-0637	36	0.00	0.00	0.00	0.00
56	Planar	HDMI Cable 3FT	903-1511	140		0.00		0.00
57	Planar	HDMI Cable (3M)	903-1399	4	0.00	0.00	0.00	0.00
58	Planar	Corner Trim For DL2 Series Cabinet HORIZ Trim for DL2 Cabinet	572-4572	4	0.00	0.00	0.00	0.00
59	Planar	Horizontal Trim for DL2 Cabinet	572-4932	12	0.00	0.00	0.00	0.00
60	Planar	Vertical Trim for DL2 Cabinet	572-4934	12	0.00	0.00	0.00	0.00
61	Planar	Horizontal Trim Bracket for DL2 Cabinet	572-4935	49	0.00	0.00	0.00	0.00
62	Planar	Vertical Trim Bracket for DL2 Cabinet	572-4936	26	0.00	0.00	0.00	0.00
63	Planar	DLX 1.8 LED Tile- Spares	998-0704	29	0.00	0.00	0.00	0.00
64	Planar	DLX 1.8 LED Cabinet-Spares	998-0702	7	0.00	0.00	0.00	0.00
65	Planar	VCS Video Wall Processor with 8 DP IN and 8 DP OUT	VCS6-ENT 8in, 8 out	1	0.00	0.00	0.00	0.00
66	Extron	DTP HDMI 4K 330 RX Receiver/RX Receiver Box	60-1331-12	2	0.00	0.00	0.00	0.00
67	Planar	UR8651-MX, 86" UHD 4K Native Commercial Grade Flat Panel Display, 24X7, Mediaplex Processing, Speakers, OPS Slot, RS232 Control Port with IR Remote	997-8520	4	0.00	0.00	0.00	0.00
68	Premier Mounts	Heavy Duty XL Dual Articulating Arm Flat Panel Display Wall Mount	997-7969	4	0.00	0.00	0.00	0.00
69	Planar	HD Base-T HDMI Extender set with TX Transmitter (Into VCS at rack) Rx Receiver at Display	750-2238	4	0.00	0.00	0.00	0.00
70	Planar	MISC Cables, Connectors, screws and install materials (1 LOT)		1	0.00	0.00	0.00	0.00
71	Planar	Three (3) Year Gold Program Onsite Service and Maintenance Agreement w/8 Hour Onsite Service Response Time		1	0.00	0.00	0.00	0.00
72	Per SOW	End user Training for Video Wall, VCS and Control System (16HRS)	Per 8.1	1	0.00	0.00	0.00	0.00